

ADDENDUM #1



PROJECT: 2019 Cerise Park Trail Improvements
BID NO: 19-001
FROM: John Malloy
DATE: 1-29-2019

Questions and Answers

1. *Item 2.1.1 refers to drainage swales being lined with 3" cobble.*
Answer: Instead of using 3" cobble, 3-6" angular rock should be used in these drainages as well as armoring outflow areas.
2. *Item 1.2 and 2.1.2 in the RFP references fencing specifications. The specification for fencing has changed.*
Answer: Instead of using split rail cedar fence, lagged round rail fence will be used. The fence posts should be 4", 4'6" in height (above ground) and 2' in the ground. There will be two 3" round rails at 24" and 48".
3. *Question: "Do you have elevation data for the trail segments?"*
Answer: Trail elevation data is not available at this time and the City is not in a position to provide this data prior to the close of the bid. Contractors are invited to survey the project area as needed for accurate bidding purposes.

Acknowledgement in Receipt of Addendum

FIRM NAME: _____

BY:(Printed) _____

BY:(Signature) _____ TITLE: _____

Note: A signed acknowledgement in receipt of this addendum **MUST** be included with your bid proposal.