

# ADDENDUM #1



**PROJECT:** West Main Underpass Decorative Shotcrete Wall  
**BID NO:** 19-050  
**FROM:** Scott Murphy  
**DATE:** February 5, 2020

---

## Questions and Answers

1. *What kind of surface preparation is necessary for the existing soil nail wall before placement of the new decorative face?*

**Answer:** The existing shotcrete wall should be pressure washed clean at least 24 hours prior to placement of the new shotcrete.

2. *Is there a detail available for the contact between the top of the decorative shotcrete wall and the bottom of the coping?*

**Answer:** The design team did not specifically detail this joint as its configuration would depend on how the wall is formed and the contractor's methodology to control grades. The City asks that the detail for this joint be proposed by the shotcrete contractor and approved by the design engineer. In general, the City is open to some sort of chamfer joint or overhang and the joint would require a flexible sealant (Sikaflex or similar) to limit the potential for water intrusion and freeze/thaw action.

## Clarifications and Additions

1. None this addendum.

## Plan Revisions

1. The original bid due date was accidentally set on a City Holiday (President's Day) where mail service will not be available. As a result, the bid due date is extended to 2:00 PM February 18, 2020 at Montrose City Hall.

## Acknowledgement in Receipt of Addendum

FIRM NAME: \_\_\_\_\_

BY:(Printed) \_\_\_\_\_

BY:(Signature) \_\_\_\_\_ TITLE: \_\_\_\_\_

Note: A signed acknowledgement in receipt of this addendum **MUST** be included with your bid proposal.