

ADDENDUM #1



PROJECT: Black Canyon Golf Course Front 9 Irrigation Pump Assembly
BID NO: 20-017
FROM: Tom Young
DATE: December 30, 2020

Questions and Answers

- 1. The Ethernet communication module; is the necessary? Meaning is the system tying to Rainbird central control? Or is it used for strictly remote monitoring? We can provide an Ethernet module for remote monitoring via our standard system. Will this feature be utilized?*
Answer: The Ethernet communication module will be used strictly for remote monitoring.
- 2. The flow meter listed is a paddle wheel style flow meter we typically utilize a magnetic flow meter that has no moving parts. Will this be acceptable?*
Answer: Yes, a magnetic flow meter would be acceptable.
- 3. We can offer a Wye strainer but would like to offer a true self-cleaning style filter if this is an option? Wye strainers are not very efficient at fully cleaning.*
Answer: Yes, a true self-cleaning filter would be acceptable. Please provide details on the filter in your proposal.
- 4. There is not much listed in the quote sheet for what is required with motor controls. Our standard offering is to utilize VFD's for all motors. Is this acceptable?*
Answer: Yes, VFD's are preferred on all motors.

Clarifications and Additions

1. The initial posting of the project bid packet and announcement had an incorrect bid opening date of August 5, 2020. This information has been corrected on the announcement and bid packet posted on the City's website. The correct bid opening date is January 14, 2021.

Acknowledgement in Receipt of Addendum

FIRM NAME: _____

BY:(Printed) _____

BY:(Signature) _____ TITLE: _____

Note: A signed acknowledgement in receipt of this addendum **MUST** be included with your bid proposal.