



**LA RAZA PARK IMPROVEMENTS
PROJECT BID FORM (Exhibit C)**

Project Number:
Bid Number: 21-002

January 25th, 2021

Bidder: _____

	Line Item	Contract Item	Unit	Project Total	Unit Price	Extension
Removals	1	Unclassified Excavation and Off-Site Disposal (a)	CY	10		\$0.00
Fill & pave	2	Aggregate Base - CDOT Class 6 (Include moisture conditioning, compaction and testing)	Ton	96		\$0.00
	3	Concrete Mix	CY	65		\$0.00
Sports Court	4	Coatings are to be Nova Play in conjunction with Nova Play II	LS	1		\$0.00
	5	American Super Sports First Team Legend Intesity Basketball Goal - 72 Inch, FT267 42" x 72" Perforated Aluminum Backboard, FT172D Unbreakable Fixed Rim with net, FT1850 Legend 6" x 6" Extension Arm with 66" extension length and BaFT1106 6" x 6" Square Post	EA	2		\$0.00
Site Amenities	6	Dumor 165 Series PL with Cedar recycled plastic slats, 6' in length and surface mounted.	EA	1		\$0.00
	5	Solar light Greenshine LITA GS-LED-L30 in-ground mount	EA	5		\$0.00
Misc.						
	8	General Conditions and Mobilization	LS	1		\$0.00
	9	Final Site and Adjacent Property Restoration (Incl. restoration of all disturbed areas within and outside of project area and staging areas not specifically paid for elsewhere to pre-project condition and final grading to match adjacent improvements)	LS	1		\$0.00
	10	Payment and Performance Bond	LS	1		\$0.00
	11	Contingency ^(d)	LS	10%	\$0.00	\$0.00
					TOTAL	\$0.00

Keved Notes

- (a) Item to be paid based on plan quantities, item will not be measured in the field, contractor to verify quantities prior to bid. Quantities presented for soils do not contain a fluff or loss factor
- (b) Item to be paid based on area of fabric complete in place including 3' of overlap at seams
- (c) To be paid based on weight tickets
- (d) Taken as 10% of all items above this line