

ADDENDUM #2



PROJECT: Woodgate Road Realignment Project
BID NO: 21-011
FROM: Scott Murphy
DATE: March 10, 2021

Questions and Answers

1. None this addendum

Clarifications and Additions

1. None this addendum

Plan Revisions

1. Sheet 10, Note 1 references the construction of a 2" ball valve and drain line between an irrigation pump and the new 8" irrigation drain line ("Irrigation Line 1", see Sheet 16). We discovered today that the sprinkler contractor currently working with the homeowner to relocate this pump system will install the ball valve on this line and a small stub coming out of it when they relocate the pump in the next few weeks. As a result, the City contract may tie onto the downstream end of this stub for the drain line and does not need to supply the ball valve.
2. Modify the rim elevation on storm drain Inlet 2 from 5866.24' to 5865.50', grade locally around the grate for this area to drain, and adjust the retaining wall blocks along the western side to corral around the inlet. This elevation matches the approximate elevation of the existing drain, just translated towards the east.
3. The brick fence column (see Sheet 23) shall be 12"x18" instead of 18" square shown on the plans. The 18" face is parallel to the roadway.

Acknowledgement in Receipt of Addendum

FIRM NAME: _____

BY:(Printed) _____

BY:(Signature) _____ TITLE: _____

Note: A signed acknowledgement in receipt of this addendum **MUST** be included with your bid proposal.