

# ADDENDUM #1



**PROJECT:** 6700 Road Extension  
**BID NO:** 22-026  
**FROM:** Scott Murphy  
**DATE:** December 8, 2022

---

## Questions and Answers

1. *When does the irrigation water typically turn on? Is there a chance the box culverts could be installed before irrigation water is turned on?*

**Answer:** Irrigation water turns in to the AMK Lateral (ditch along Miami Road) typically around mid-March. Water runs in the H-Drain year-round but is elevated during the same irrigation season. Depending on the lead times of the box culverts, it may be feasible to have this work completed by mid-March. At a minimum, it is recommended that the western tie-in cast-in-place box on the AMK lateral be constructed before mid-March in order to simplify bypass pumping operations should the need arise to install the box culvert after irrigation water has started to run in the ditches.

## Plan Revisions

1. Given the anticipated long lead time for procurement of the project's box culverts, the City is able to provide written authorization to the recommended contractor to place the order for the box culverts by end of day on January 12, 2023. Payment for these items will still run through the contract according to the bid form.
2. The City was able to walk the spoils fill and staging area with the landowner after posting the initial bid. The owner has confirmed that we will remove all trees and vegetation within the spoils fill and staging area (see Sheet 5 and general notes section regarding Removals and Clearing) with the following exceptions:
  - a. An existing spruce tree approximately 10 feet tall outside of the road area may remain. Contractor shall remove several feet of limbs near the trunk and fill loosely around the tree trunk to match adjacent spoils fill grade (no compaction needed around tree).
  - b. An existing spruce tree approximately 6 feet tall within the road footprint shall be transplanted to the northeastern corner of the spoils fill area. Transplant by digging around the root ball beyond the drip line and transplant to an excavated hole 3x the rootball size and backfilled with topsoil stripped from the site.

Costs for the tree accommodations and transplanting shall be included in the *Removal of Trees and Stumps* line item on the bid form.

## Acknowledgement in Receipt of Addendum

FIRM NAME: \_\_\_\_\_

BY:(Printed) \_\_\_\_\_

BY:(Signature) \_\_\_\_\_ TITLE: \_\_\_\_\_

Note: A signed acknowledgement in receipt of this addendum **MUST** be included with your bid proposal.