

ADDENDUM #4



PROJECT: 6700 Road Extension
BID NO: 22-026
FROM: Scott Murphy
DATE: December 28, 2022

Questions and Answers

1. *Can you clarify where volume quantities for clearing/grubbing are to be included on the bid form? How do these relate to the roadway excavation Line Items 11 and 12?*

Answer: All soil volume produced as part of clearing and grubbing operations shall be included in the clearing and grubbing Line Item 3 on the bid form. This shall include all soil removal and stripping required within the roadway footprint (incl. embankment slopes), disturbance areas (incl. retention pond), and spoil fill areas. On the plans this is presented as 6 to 8 inches thick but the intent is to remove the organics as necessary to provide a suitable starting surface to build embankment or prepare subgrade. If less stripping is required to get through the organic layer (as is likely to be the case at the southern end of the project), there is no need to strip additional material below the organic layer. Replacement of the stripped organic materials will be paid on the final site restoration line of the bid form (Line Item 93) and shall include the retention pond area.

For the excavation Line Items 11 and 12, these quantities were prepared within the AutoCAD Civil3D model as the volume between the subgrade and starting surfaces. The starting surface was defined as the existing ground less 6 inches of stripped organics.

Acknowledgement in Receipt of Addendum

FIRM NAME: _____

BY:(Printed) _____

BY:(Signature) _____ TITLE: _____

Note: A signed acknowledgement in receipt of this addendum **MUST** be included with your bid proposal.