

ADDENDUM #9



PROJECT: 6700 Road Extension
BID NO: 22-026
FROM: Scott Murphy
DATE: January 9, 2023

Questions and Answers

1. *Can you provide some additional clarification on bid Line Item 77 (Irrigation Conduits) and Line Item 78 (2 qty HDPE Conduits)?*

Answer: Yes – additional clarification is below:

- Line Item 77: These are the crossings on every other lot line at the northern half of the project where there will be future residential lots. Each crossing to be paid would include side by side 4" SDR35 pipes, 110 LF each pipe for a total of 110 LF trench and 220 LF of pipe at each. Delineator posts are T-posts painted purple.
- Line Item 78. This is for the trenches where we need to drop in empty conduits. The trench itself would be paid on Lines 73 or 74. If we need to add the conduits, for every foot of trench there would be three conduits side by side. For example, if it was a 250 foot run there would be 250 feet of trench paid on 73 or 74, 250 feet of line item 78 paid, and the trench would have three 250 LF long 2 inch conduits in it side by side (750 LF of conduit total). This was setup separate from the trench payment since only some trenches will include the empty HDPE conduits. Others may be dry utility trenches only with items placed by the utility companies.

Acknowledgement in Receipt of Addendum

FIRM NAME: _____

BY:(Printed) _____

BY:(Signature) _____ TITLE: _____

Note: A signed acknowledgement in receipt of this addendum **MUST** be included with your bid proposal.